

Carrington Winterization process 2017-2018

Need pics of each item below * for client approval and note if Pressure does not hold so we can get approval on repairs**

Standard Dry Winterization: Ensure all steps are completed for approval:

*****Shut Water OFF at Curb and Main**

*****Zip Tie Water shut off valves in OFF position**

*****Disconnect water meter and cap lines (if allowed by local code)**

*****Drain Water heater**

*****Drain Remaining plumbing system – All Fixtures**

*****Pressure Test the system: MUST hold at 30-35 PSI for 30 min to pass**

*****ANTI- FREEZE: Pour pink non-toxic anti freeze down all fixtures, drains, appliances Dishwasher, Toilets**

*****POST Winterization notices on ALL FIXTURES and Electric Panel:**

*****(Never use DUCT tape, only BLUE tape neatly with the Winterization Tags I will send out)**

*****Post Winterization notice on front window:**

Take pics of each process and documents posted *Requirement*****